

MICROCOPY RESOLUTION TEST CHAIN NATIONAL BURLAU OF STANDARDS 1963 -

COCCUPANT TRANSPORTED POSTERIOR TRANSPORTED PROCESSING PROPERTIES PROCESSING

A SIMULATION STUDY OF A LIMITED SENSING RANDOM ACCESS ALGORITHM FOR A LOCAL AREA NETWORK WITH VOICE USERS

BY

ROBERT M. SPILLERS
B.S.E., United States Military Academy, 1979

# **THESIS**

Submitted in partial fulfillment of the requirements for the degree of Master of Science in Engineering in the Graduate Studies Program of the College of Engineering University of Central Florida Orlando, Florida

Fall Term 1987



DISTRIBUTION STATEMENT A

Approved for public releases
Distribution Unfunteri

88 5

A STATE OF THE STA	en e	i kanada kan	<mark>ĬĬĸĸĬŢĸŦŖĠĸĸŎĊĸĸ</mark> ĬĸŎĸŎĸŎĸŎ	<u> </u>	Barranatar Paktra	or Coeres	
SECURITY CLA	SSIFICATION O	F THIS PAGE					
			DOCUMENTATIO	N PAGE			Form Approved OMB No. 0704-0188
1a. REPORT S	ECURITY CLASS	SIFICATION		16. RESTRICTIVE	MARKINGS		<del></del>
UNCLAS				2.5550			
2a. SECURITY	CLASSIFICATIO	N AUTHORITY		3 DISTRIBUTION	N/AVAILABILITY	OF REPORT	
2b. DECLASSI	FICATION / DOV	VNGRADING SCHEDU	JLE		FOR PUBLIC		Ε;
4 PERFORMIN	G ORGANIZAT	ION REPORT NUMB	FR/S)	5. MONITORING	TION UNLIM		IMRER(S)
4. 7 2 01	TO ONORHIZA	TOTAL NET ON THOMAS	LIN(3)	J. W.S.W. S.W.			S
6a. NAME OF	PERFORMING	ORGANIZATION	6b. OFFICE SYMBOL	7a. NAME OF M	IONITORING OR	SANIZATION	
STUDEN			(If applicable)	HQDA, MIL	PERCEN		
HQDA, N	ILPERCEN	<del></del>	DAPC-OPA-E	ATTN: DA			
	(City, State, an			7b. ADDRESS (C	=	IP Code)	
	OVALL STRE ORIA, VA			200 STOVA	LL STREET A. VA 223:	2.2	
ALLANI	KIA, VA	22332		KUCAKIDKI	n, vn 223.	) _	
8a. NAME OF ORGANIZA	FUNDING/SPO ATION	DNSORING	8b. OFFICE SYMBOL (If applicable)	9. PROCUREMEN	IT INSTRUMENT	IDENTIFICA	TION NUMBER
SAME AS			<u> </u>	ļ			·····
8c. ADDRESS	City, State, and	d ZIP Code)		10. SOURCE OF			TIMORY LINET
SAME AS	5 7ь			PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.	WORK UNIT ACCESSION NO.
11. TITLE (Inc	lude Security C	lassification)	· · · · · · · · · · · · · · · · · · ·		<del></del>		
WITH VO	DICE USERS	DY OF A LIMIT	ED SENSING RANDO	OM ACCESS AL	GORITHM FO	R A LOCA	L AREA NETWORK
12. PERSONAL	, ,						
CPT ROE		ILLERS, USA	OVERED	14. DATE OF REPO	ORT /Year Mont	h Day) 15	. PAGE COUNT
136. 1116 01	FINAL		87 TO DEC 87		DEC 11	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	38
16. SUPPLEM	NTARY NOTAL			1,707	0130_11		
THESIS			AL FLORIDA FO	OR MSEE.			
17.	COSATI		18. SUBJECT TERMS (	Continue on rever	se if necessary a	ind identify	by block number)
FIELD	GROUP	SUB-GROUP	RANDOM ACCESS				
		<del></del>	LOCAL AREA NE	ETWORK			
19. ABSTRACT	(Continue on	reverse if necessary	and identify by block n	umber)			<del></del>
Tr 1.		of this	da ka amalimi	A1	<b>c</b>	1.4 4 1	
			is to evaluate rea network with				
			n local area net				
			voicepackets car				
because	of the re	equirement th	at a voice "data	stream" mu	st be playe	ed out a	t the receiver.
			its established				
simulat	ion study	finds the nu	mber of voice us	sers that a	network car	suppor	t, provided the

packet loss rate that can be tolerated by a customer does not exceed a certain threshold. Finally, a comparison is made with the simulation results of this algorithm with other commonly used protocols.

20. DISTRIBUTION/AVAILABILITY OF ABSTRACT  UNCLASSIFIED/UNLIMITED  SAME AS RPT		21. ABSTRACT SECURITY CLASSIFICATION	TION
444. NAIVIE OF RESPONSIBLE INDIVIDUAL	DTIC USERS	UNCLAS 22b TELEPHONE (Include Area Code)	22c. OFFICE SYMBOL
CPT ROBERT M. SPILLERS		301-267-3592	HSNA EE DEPT

**DD Form 1473, JUN 86** 

ACCUSANCE CONTRACTOR OF STANCES OF STANCES OF STANCES

Previous editions are obsolete.

SECURITY CLASSIFICATION OF THIS PAGE

# **ABSTRACT**

The purpose of this work is to evaluate the performance of a limited sensing random access algorithm in a local area network with voice users. Random access algorithms have proven to be very efficient in local area network environments with data users. However, in contrast to data packets, voice packets cannot be allowed to experience long delays, because of the requirement that a voice "data stream" must be played out at the receiver. If a voice packet does exceed its established maximum delay, it is discarded. This simulation study finds the number of voice users that a network can support, provided the packet loss rate that can be tolerated by a customer does not exceed a certain threshold. Finally, a comparison is made with the simulation results of this algorithm with other commonly used protocols.

DT"

Acces	sion	For	,
NTIS	GRA8	ķΙ	V
DTIC	TAB		ũ
Unanr	nounce	∍đ	ä
Justi	triont	ticn	
· ·	JAVOS	1.1 0	

,, (1

# TABLE OF CONTENTS

LIST	OF TABLES								 •	•	•	•	•	iv
LIST	OF FIGURES .								 •	•	•	•		٧
Chapt I.	er INTRODUCTION								 •					1
II.	THE MODEL .								 •	•			•	4
III.	THE ALGORITHM First-Ti	me Tra	nsmi	 issio	n Ru	ile.	· ·				•			7
IV.	PERFORMANCE M	EASURE	:s -	SIMU	ILAT]	ON F	RESUL	.TS		•	•	•		15
٧.	DISCUSSION . The Mode Simulati Comparis	l on Res	 ults						 •					25 26
VI.	CONCLUSION .						•		 •			•	•	29
Appen A.	dices DERIVATION OF	P AND	T						 •	•		•	•	31
В.	SIMULATION PR	OGRAM	LIST	TING						•	•	•		32
REFER	ENCES													38

3		
	LIST OF TABLES	
<u> </u>	1. Packet Loss Rate for a 1MBPS Network	1
Š.	2. Packet Loss Rate for a 10MBPS Network	2
Ø X	3. Comparison of Circuit Capacity	2
8		
C 220		
8 8		
666		
<b>8</b>		
2		
Á		
<b>1</b>		
6033	<b>4</b>	
× ×	iv	

# LIST OF FIGURES

1.	Packet Movement with a Success	. 13
2.	Packet Movement with a Collision	. 12
3.	Packet Movement with an Idle	. 13
4.	Packet Loss Rate Versus Number of Circuits as a Function of Packet Length for a 1MBPS Network	. 1
5.	Packet Loss Rate Versus Number of Circuits as a Function of Packet Length for a 10MBPS Network	. 18
6.	Comparison of Packet Loss for LSAVU Versus CSMA/CD and GBRAM on a 1MBPS Network With a Packet Length of 96 Bytes	. 2
7.	Comparison of Packet Loss for LSAVU Versus CSMA/CD and GBRAM on a 10MBPS Network With a Packet Length of 96 Bytes	9.
	UI JU DY LC3	. 2.

# CHAPTER I

# INTRODUCTION

Local area networks (LANs) have been used extensively in the past few years for data communications. Using a single, multi-access channel, the LAN can support a large number of users at very high data rates. Musser shows the technical feasibility of utilizing a LAN as a multi-drop local subscriber loop for a Private Automatic Branch Exchange (PABX).[1] His objective was to replace the multiple twisted pairs being pulled from the PABX with a single coaxial cable. Subscriber terminals (voice users) may then simply tap into the cable at each location. Indications show that as the cost of the tap and other electronics involved in digital telephony decrease, while labor costs of pulling wires increase, implementation of the above arrangement will become cost-effective.

represent consecution of the second

K-555552 | 15555-552 | 15555-566

It is worth noting that the "LAN arrangement," proposed by Musser, can support a variety of users (i.e., voice users, data users, etc.).[1] In other words, any user (voice, data, or other) who wants to access the channel, simply taps onto the cable. Considering the fact, that future communication networks are expected to handle a variety of traffic types, and that an enormous effort is currently being undertaken to incorporate voice

and data on the existing telephone network, the "LAN arrangement" is a step towards the right direction.

Musser examined the performance of two well known protocols. [1] A carrier sense multiple access with collision detection (CSMA/CD) protocol (specifically Ethernet) [2], which is a random access (contention) scheme and the group broadcast recognizing access method (GBRAM) protocol [3], which is a decentralized demand-assignment (contention-free) scheme. In contrast to data packets, voice packets cannot be allowed to experience long delays, because of the requirement that the receiver buffers not empty, so that "stream data" can be played out at the receiver (the telephone earpiece).[1] Therefore, voice networks must be operated on packet-loss basis. The performance curves corresponding to CSMA/CD and GBRAM by Musser are plots of the packet loss rate versus the number of voice circuits, which are active on the channel.[1]

This thesis examines the performance of a limited sensing random access algorithm for the "LAN arrangement" proposed by Musser.[1] This random access algorithm (RAA) was first proposed by Merakos, who analyzed its performance in a LAN environment with data users, under the assumption of a slotted channel.[4] The same RAA was analyzed by Georgiopoulos for the more realistic case of an unslotted channel.[5] This RAA has a number of advantages. First, it is a limited sensing RAA, which implies that a voice user does not have to sense the channel unless it has a packet to

transmit. Secondly, it has been proven to be very effective in a LAN environment with data users for both slotted and unslotted channels.[4][5] Thirdly, it is a stable algorithm for the infinite population user model.[4][5] Fourthly, it has last-come-first-serve characteristics, which is desirable in LANs with voice users because voice packets cannot experience long delays.[4] Finally, as the results of this thesis will show, it outperforms CSMA/CD and GBRAM in a LAN environment with voice users.

gerral becomes. Versicaed versicaed interestes, cerestes, cerestes acceptes, ceresces acceptes, ceresces array

# CHAPTER II

# THE MODEL

consecute and second of the second se

This model assumes that the two ends of a voice circuit generate R bits/second of traffic into the system. Voice packets of constant size L bits are assembled at regular intervals and sent to the voice user buffer. A buffer size of one packet is required at each voice user site. A packet from an active voice user will be generated at every F = L/R seconds. Since a buffer size of one packet is provided at each user site, a constraint of F seconds packet lifetime must be imposed at the transmitter. A packet with transmission delay longer than F seconds results in a packet loss. Packets generated from all active voice users are stored in the appropriate buffers and then transmitted over the common cable. The model assumes that the caracity of the cable is C bits/seconds; hence, a packet will require a slot length of  $\Delta$  = L/C seconds for its transmission. The length of the cable is equal to d km. The end-to-end propagation delay (the time it takes for a packet to traverse the cable from one end to the other) is denoted by  $\alpha$  and is equal to d/v, where v is the speed of light.

To facilitate the presentation,  $\alpha$  is taken to be the unit of time ( $\alpha=1$ ). To express the parameters F and  $\Delta$  in units of time, let:

$$F = T * \alpha \tag{1}$$

and

$$\Delta = \mathbf{P} * \alpha \tag{2}$$

Now, the maximum packet lifetime equals T units of time and the packet transmission time equals P units of time. Without loss of generality, P and T are assumed to be integers.

During the simulation, the system generates N packets (N conversations are active) every T units of time, and these packets are uniformly distributed over the period of T units of time. The same packet generation model was also adopted by Musser.[1]

To simplify the simulation, the following assumptions were made:

- A1. The channel is divided into slots.
- A2. The length of a slot is equal to the end-to-end propagation delay  $\alpha$ .
- A3. Voice users are allowed to initiate packet transmissions only at the beginnings of slots.

This model considers limited channel sensing and ternary feedback. That is, it assumes that the voice users sense the channel only when they have a packet to transmit, and they can determine which one of the following occurs:

- a). no transmission (idle period)
- b). a single transmission (success)
- c). two or more transmissions (collision)

An idle period corresponds to the end-to-end propagation delay and lasts one unit of time (one slot). The length of a successful transmission corresponds to the packet transmission time plus one unit of time to inform all the users that the channel is clear. That is, P + 1 units of time, or P + 1 slots. In the case of a collision, let  $\beta$  denote the fraction of each packet (in units of time) that gets transmitted during the collision before the transmitting users abort their transmissions by detecting the interference. A collision lasts until all monitoring users are aware of the collision and the channel clears. That is,  $\beta$  + 1 units of time. For local networks using a cable, where users can listen to their own transmission, it is commonly assumed that  $1 \leq \beta < P$ . The users have early collision detection capabilities, and  $\beta$  is referred to as the collision detect time. This model assumes that  $\beta$  = 1.

# CHAPTER III

# THE ALGORITHM

The execution of the algorithm governing the accessing of the channel is divided into a series of algorithm steps. Let  $t_i$  ( $i=0,1,2,\ldots$ ) denote the instants at which consecutive algorithm steps begin. These algorithm instants always coincide with the beginning of some slot. At the beginning of the operation of the system let  $t_0=0$ ,  $t_1=1$ . For  $i\geq 1$ , let:

$$t_{i+1} - t_i = \begin{cases} 1 & \text{if the ith algorithm step is idle} \\ P+1 & \text{if a successful transmission occurs at the ith algorithm step} \\ \beta+1 & \text{if a collision occurs at the ith algorithm step} \end{cases}$$

All voice users in the network are active (see model in Chapter II). A packet may either be new or blocked. A new user at time  $t_i$  is one whose packet arrived during step i-1. A blocked user at  $t_i$  is one whose packet has collided before step i. Since each voice user in the network has a buffer with a capacity of one packet, the terms user and packet can be used interchangeably.

<u>Definition</u>: A packet in the system is called "legitimate" if its delay is smaller that the maximum packet lifetime, T.

A packet whose delay is larger than the maximum packet lifetime, T, is discarded from the system. Each "legitimate" packet has a counter, which assumes non-negative integer values. A "legitimate" packet is in the system if the counter value of the packet has already assumed a non-negative value. Let  $CI_i$  denote the counter indication of an arbitrary packet at algorithm instant  $t_i$ . The following operational rules are defined:

- 1. At instant  $t_i$ , all "legitimate" packets with  $CI_i = 0$  are transmitted.
- 2. All users with "legitimate" packets in the system, sense the channel and act as follows:
- a. If a successful transmission occurred at step i, then the "legitimate" packet with  $CI_i = 0$  leaves the system. All "legitimate" packets with  $CI_i = r$   $(r \ge 1)$  increment their counters by m-1  $(m \ge 1)$  at instant  $t_i+1$ , and set  $CI_{i+1} = r+m-1$ , where m is an integer parameter.
- b. If a collision occurred at step i, then every "legitimate" packet with  $CI_i=0$ , independently of the others, sets its counter value to m-1+N, where N is an integer random variable uniformly distributed on  $\{1, 2, \ldots, n\}$ , and n is an integer parameter such that  $n \geq 2$ . Each of the "legitimate" packets with  $CI_i=r$   $(r \geq 1)$  increment their counter by m+n-1. Thus,  $CI_{i+1}=r+m+n-1$ .

c. If algorithm step i is idle, then all "legitimate" packets with counter values  $CI_i > 1$  decrement their counter values by one  $(CI_{i+1} = CI_i - 1)$ .

The integers m and n are design parameters to be optimized. To complete the description of the algorithm, the rule by which a new "legitimate" packet will determine the instant for its initial transmission attempt will now be specified.

SOCIOSIO DE PROPERTO DE SOCIEDA DE SOCIO DE SOCIE DE SOCIO DE SOCIE DE SOCIO DE SOCIEDA DE SOCIO DE SOCIEDA DE SOCIO DE SOCIEDA DE SOCIO D

# First-Time Transmission Rule

When a new "legitimate" packet arrives during a slot at a voice user site, the user senses the channel at the beginning of the next slot. If the channel is idle, the packet sets its counter value to 0, and therefore, attempts transmission at the same instant. If the channel is sensed busy, the user waits until the channel is sensed idle for the first time (at the beginning of some slot), and only then the user sets the counter value of its packet to M, where M is an integer random variable uniformly distributed on {0, 1, ..., m-1}.

As it can be seen from the description above, for the implementation of the algorithm in a distributed fashion, it suffices for each packet to have one counter and two random number generators.

The general operation of the algorithm is perhaps better illustrated by introducing the concept of a "stack" as it was first done by Tsybakov.[6] A stack will be understood to mean an

abstract storage device, consisting of an infinite number of cells, labeled 0, 1, 2, .... The number of packets that a cell can accommodate is unrestricted. At each algorithm instant,  $t_i$ , the kth cell of the stack contains the packets with  $CI_i = k$  ( $k \ge 0$ ). Packets are eventually successfully transmitted (unless they are discarded) after moving through the cells of the stack in accordance with the rules of the algorithm.


In figures 1, 2, and 3, by using the concept of the stack, a successful, a collision, and an idle step, respectively, is shown.

In Figure 1, there is one packet in the transmission cell ( $X_1$  = 1) at time  $t_i$ . Therefore, the algorithm steps ahead to  $t_i$  + P + 1, and any new packet arrivals during the successful transmission enter the first m cells of the stack (note that new packets arriving in the slot immediately before  $t_i$  + P + 1 see the channel idle and enter the transmission cell). All previous "legitimate" packets in the stack increase their counter values by m-1, to make room for the new packet arrivals.

In Figure 2, there are K (K  $\geq$  2) packets in the transmission cell at time  $t_i$ . These packets collide, and are distributed in n cells of the stack, after the algorithm steps ahead to  $t_i$  + 2. New packet arrivals are distributed as in Figure 1 into the first m cells of the stack, while old packets in the stack move up m + n -1 cells.

In Figure 3, at time  $t_i$ , there are no packets in the transmission cell ( $X_1 = 0$ ), and there are no new arrivals before

PARKERSE



CONTRACT DESCRIPTION TO SECOND

Paragraphy and the second of t

Figure 1. Packet Movement with a Success.





Figure 2. Packet Movement with a Collision.



 $t_i$ . The algorithm steps ahead one slot  $(t_i+1)$ , and all the packets in the stack (if any) move down one cell, while N (N  $\geq$  0) new packet arrivals enter the transmission cell.

The above described algorithm will be referred to as LSAVU (Limited Sensing Algorithm for Voice Users) in this thesis.

# CHAPTER IV

# PERFORMANCE MEASURES - SIMULATION RESULTS

The most important performance measure of the effectiveness of LSAVU is the packet loss rate (averaged over all active voice circuits) versus the number of active voice circuits. The packet loss rate is defined to be the percentage of voice packets discarded by LSAVU. This performance measure was also adopted by Musser to test the effectiveness of the CSMA/CD and the GBRAM protocol.[1]

For the simulation, the model of Chapter II was adopted. The values of  $\alpha$ ,  $\beta$ , P, T are needed to perform the simulations. According to the model in Chapter II,  $\alpha = \beta = 1$  unit of time. For the values of P and T, the following cases are considered:

P = 231, T = 3600Case 1: P = 116, T = 1800Case 2: P = 58, T = 900Case 3: P = 29, Case 4: T = 450Case 5: P = 24T = 3600Case 6: P = 12.T = 1800Case 7: P = 6, T = 900Case 8: P = 3. T = 450

In cases 1 through 8, the length, d, of the cable is taken to be equal to 1.0 km. Furthermore, in cases 1 through 8 each voice circuit generates R=64,000 bits/second of traffic into the system. In cases 1 through 4, the capacity of the cable is C=1.0 Mbps. In cases 5 through 8, C=10.0 Mbps. In cases 1 and 5, the

packet length is L = 768 bits (96 bytes); in cases 2 and 6, L = 384 bits (48 bytes); in cases 3 and 7, L = 192 bits (24 bytes); and in cases 4 and 8, L = 96 bits (12 bytes). The same d, R, C, and L values were also adopted by Musser.[1] In Appendix A, the derivation for the values of P and T for cases 3 and 7 is shown.

It was determined from experimentation that 10,000 voice packets were sufficient to produce reliable simulation results. Different values of m and n were also checked, and it was found that for all cases (1-8), the optimum values were:

$$m_{opt} = 1$$

School Section (Section )

$$n_{opt} = 3$$

The optimum values  $m_{opt}$  and  $n_{opt}$  of m and n were the ones which produced the smallest packet loss rates for each case simulated. The LSAVU algorithm with m =  $m_{opt}$  = 1 and n =  $n_{opt}$  = 3 is denoted as LSAVU opt.

In Figure 4, the packet loss rate versus the number of active voice circuits curve corresponding to the LSAVU algorithm, when the cable has a capacity of C=1.0 Mbps (cases 1-4) is drawn. In Figure 5, the packet loss rate versus the number of active voice circuits curve corresponding to the LSAVU algorithm, when the cable has a capacity of C = 10.0 Mbps (cases 5-8) is shown. Tables 1 and 2 give the numerical data corresponding to figures 3 and 4, respectively.




Figure 4. Packet Loss Rate Versus Number of Circuits as a Function of Packet Length for a 1 MBPS Network.




Figure 5. Packet Loss Rate Versus Number of Circuits as a Function of Packet Length for a 10 MBPS Network.

CARACTER CONTRACTOR OF THE CON

TABLE 1 PACKET LOSS RATE FOR A 1MBPS NETWORK

				19			
•							
				TABLE 1			
		PAC	KET LOSS	RATE FOR		ETWORK	
	CIDC	UITS:	12	1.4	1 5	16	17
		T	13	14 PACK	15 ET LOSS RA	16 TF (%)	17
		<del></del>					
	231	3600	0	0	0	4.03	9.7
	116	1800	0	0	0	6.08	10.2
	58	900	0	0	2.45	8.59	13.1
	29	450 	0	1.88	7.68	11.78	21.0

TABLE 2
PACKET LOSS RATE FOR A 10MBPS NETWORK

Р	Ţ		PACK	ET LOSS RA	TE (%)	
CIRC	UITS:	130	132	133	134	135
24	3600	0	0.17	0.86	1.83	2.28
CIRC	UITS:	115	117	188	119	120
12	1800	0.01	0.11	0.68	1.60	2.68
CIRC	UITS:	90	92	95	97	100
6	900	0	0	0.05	0.25	2.06
CIRC	UITS:	68	70	72	73	75
3	450	0.13	0.56	1.02	2.15	3.63


COCCUMENTAL DESCRIPTIONS

In Figure 6, the packet loss rate versus the number of active voice circuits curves corresponding to CSMA/CD [1], GBRAM [1], and LSAVU opt algorithms, when the cable has a capacity of C = 1.0 Mbps and the packet length is L = 768 bits (case 1) is shown. Finally, in Figure 7, the packet loss rate versus the number of active voice circuits curves corresponding to CSMA/CD [1], GBRAM [1], and LSAVU opt algorithms, when the cable has a capacity of C = 10.0 Mbps and L = 768 bits (case 5) is shown.

Figures 6 and 7 exhibit the superior performance of LSAVU compared to CSMA/CD or GBRAM. To get a better feeling of the superiority of LSAVU<sub>opt</sub>, Table 3 shows the number of voice circuits supported by LSAVU<sub>opt</sub>, CSMA/CD [1], and GBRAM [1] at a packet loss rate of 2% for a 1.0 Mbps and a 10.0 Mbps cable and a packet length of 768 bits. Note that at a packet loss rate of 2%, LSAVU<sub>opt</sub> can support 134 voice circuits, while GBRAM can support only 125 voice circuits, and CSMA/CD can support only 94 voice circuits on a 10.0 Mbps cable.

In Appendix B, the computer program which produced the simulation results in figures 4 and 5 and tables 1 and 2 is listed.

ASSESSED POSTOCOCCO CONSTRUCTOR PERSON






Figure 7. Comparison of Packet Loss for LSAVU Versus CSMA/CD and GBRAM on a 10 MBPS Network with a Packet Length of 96 Bytes.

<del></del>	COMPARI	SON OF CIRC					
<del></del>	COMPARISON OF CIRCUIT CAPACITY						
CS	1 M MA/CD GB	BPS RAM LSAVU	I CSMA/CD	10 MBPS GBRAM	LSAVU		
Circuits	12	14 15	94	125	134		

# CHAPTER V

# The Model

The model assumed in Chapter II implies that N is the maximum number of voice circuits that can be active at the same time. Furthermore, it implies that a voice circuit is continuously in a talkspurt. Experimental results have shown that in an active conversation, a talkspurt alternates with a silence period and vice versa.[7] It has been found that talkspurts and silence periods are exponentially distributed with a mean = 1.34 and 1.67 seconds, respectively.[8] Based on the above observations, it concludes that the simulation results of Chapter IV are pessimistic. In other words, LSAVU opt can support more voice circuits than shown in figures 4 and 5 or tables 1 and 2.

The assumption that the voice packets are uniformly distributed over the maximum packet lifetime (T) is also realistic. Experimental results have shown that the voice calling generation process is Poisson.[9] Once the assumption (as in the model) is made, that the number of active voice circuits is equal to N, the N packets generated every T units of time are uniformly distributed in this interval. This is a well-known property of the Poisson process.[9]

The assumption of the slotted channel need not be made. It was adopted to simplify the simulations. Actually, it is shown that the RAA of Chapter III performs better in the unslotted LAN environment than in the slotted one.[5] The main reason for the improvement in the performance is, that in the unslotted version, the uncertainty interval (the interval over which collisions can happen) is generally smaller than the end-to-end propagation delay, while in the slotted version, the uncertainty interval is exactly equal to the end-to-end propagation delay.

CONSTRUCTION OF THE PROPERTY O

# Simulation Results

The simulation results show that values of m and n near the optimum values  $m_{opt} = 1$  and  $n_{opt} = 3$  did not affect the performance of LSAVU. The simulation results also show that for a cable of constant capacity, LSAVU opt performed better (supported larger numbers of voice circuits) for the large packet size (L = 768 bits = 96 bytes). This is a common characteristic of random access (contention) schemes in a LAN. They perform better when the ratio of the end-to-end propagation delay to the packet length becomes smaller. Finally, the simulation results show that LSAVU opt operates near 0% packet loss rate up to a point and then there is a sharp increase in the packet loss rate. Therefore, the cutoff for the number of voice circuits supported is very abrupt.

The number of voice circuits that  $LSAVU_{opt}$  supports, such that the maximum individual (per voice circuit) packet loss rate

is smaller than 2%, is almost identical to the number of voice circuits that  $LSAVU_{opt}$  supports, such that the packet loss rate (averaged over all active voice circuits) is smaller than 2%. In only one case did the individual packet loss rate lower the number of voice circuits that  $LSAVU_{opt}$  supports. In case 4 (see Chapter IV), the number of voice circuits that  $LSAVU_{opt}$  supports was reduced from 14 to 13.

# Comparisons of LSAVU with CSMA/CD and GBRAM

Musser's simulation results were conducted with slightly different parameters than the parameters used to simulate  ${\sf LSAVU}_{\sf opt}$ . In fact, Musser assumes:

- MA1. A jam time of 4.8  $\mu s$  is enforced after each collision. [1]
- MA2. A 9.6  $\mu$ s transmit/receive turnaround time is imposed. [1]
- MA3. 6 bytes of control overhead and synchronization are appended to each voice packet before it is sent over the channel.[1]

For the simulations with LSAVU, the jam time and transmit/ receive turnaround time is assumed to equal zero. Also, it is assumed that the voice packets consist of information bytes only.

Incorporating MA1 in the model of Chapter II, you simply have to increase  $\beta$  by the appropriate amount instead of letting  $\beta=\alpha$ . Incorporating MA2 and MA3 in the model, you have to increase the packet length (P) by the appropriate amount.

From experience with the RAA described in Chapter III, and the results of Table 1 in Merakos [4], it is concluded that the simulation results of figures 4 and 5 and tables 1 and 2 will not be significantly changed. Hence, the claim that LSAVU outperforms both CSMA/CD and GBRAM remains valid, especially for the 10.0 Mbps cable (see also figures 6 and 7).

# CHAPTER VI CONCLUSION

The simulation study shows that LSAVU is a viable protocol for a LAN with voice users. In fact, there are strong indications that LSAVU outperforms both CSMA/CD and GBRAM.

The next research effort in this area is to conduct a simulation study with a mixture of data users and voice users. This would be in line with the ultimate goal of integrating voice with data on a LAN using a random access algorithm (RAA).



# APPENDIX A

# DERIVATION OF P AND T

An example on how the values for P and T were found follows:

# Case 3

 $\alpha = cable length/speed of light$ 

 $\alpha = 1.0 \text{ KM/} 300,000 \text{ KM/} \text{sec}$ 

Define:  $\alpha = 1$ 

For a packet length of 24 bytes ... = 24 \* 8 = 192 bits

 $P = (192/1 \text{ MBPS}) * (1/\alpha)$ 

P = (192 \* 300,000)/1,000,000 = 57.6

Let P = 58 (next integer value)

T = (192 \* 300,000)/64,000 = 900

Note that P and T are integer values, normalized to  $\alpha = 1$ .

# Case 7

The only change from above is:

 $P = (192/10.0 \text{ MBPS}) * (1/\alpha)$ 

P = 5.76, Let P = 6

T = 900 (as above)

# APPENDIX B

# SIMULATION PROGRAM LISTING

```
c fortran program to simulate voice packet loss rate
c using the random access algorithm developed by Merakos
c implemented on a local area network.
c a(i) = packet number
c r(i) = counter value
c s(i) = packet number in stack
      integer a(100000), r(1000), s(1000), b, ct, p, nm,
     :nt, t, p1, i, p2, p3, m, n, nq, nq1, ns, op, nd
      integer j, x, ch, k, temp, oj, om, f, g, h, ix,
     :nd1(200)
      real plr, rf, ri, rp1, z, y
c generate random packets uniformly distributed over
c period 0 to t.
c nm = number of packets generated
c p = packet length
c t = max packet lifetime
c f = number of active voice circuits
      nm=10000
      p=3
      t=450
      f=73
      q=f-1
      do 62 i=1,f
      call randa(x)
      a(i)=x
      nd1(i)=0
  62 continue
c sort randon numbers into numerical order
  91 ch=0
      do 95 k=1,g
      if (a(k).le.a(k+1)) go to 95
      temp=a(k)
      a(k)=a(k+1)
      a(k+1)=temp
      ch=1
  95 continue
      if (ch.eq.1) go to 91
      do 96 m=1,f
      write (*,*) 'a(i)=',a(m)
```

SOURCE DOCUMENT STATEMENT OF THE PROPERTY OF T

```
96 continue
      do 98 m=1.f
      do 64 j=f, (int(nm/f)*f), f
      a(j+m)=a(m)+((j/f)*t)
     continue
  64
     continue
  98
      do 93 i=nm-100,nm
      write(*,*)i,a(i)
  93 continue
c ct = current time
c nst = number of packets in stack
c nd = number of packets discarded
c nt = number of packets in TX cell
c b = collision detect time
c ns = number of successfully TX packets
c nq = number of packets that have entered stack
c M and N are optimized stack values
      ct=0
      nst=0
      nd=0
      nt=0
      b=1
      ns≃0
      nq=0
      m=1
      n=4
c program checks for arrivals and new packets enter stack.
  10 if ((ns+nd).eq.nm) go to 100
c nq1 = next packet to enter stack
      nql=nq+1 if (nql.gt.nm) go to 13
      do 1 i≈nq1, nm
      if (a(i).ge.ct) go to 13
      if (a(i).ge.(ct-1).and.a (i).lt.ct) go to 12
      go to 1
  12 nq=nq+1
      nst=nst+1
      s(nst)=i
      r(nst)=0
     continue
c no packets in stack
  13 if (nst.eq.0) go to 15
c packets in stack
      if (nst.gt.0) go to 20
```

THE PROPERTY OF THE PROPERTY O

```
c increase current time and check next interval.
 15 nq1=nq+1
      if (nq1.le.nm) ct=a(nq1)+1
      if (nq1.qt.nm) ct=ct + 1
      go to 10
c discard packets in stack with delay > t.
  20 p1=0
if (nst.lt.1) go to 30
      do 2 i=1, nst
      if ((ct-a(s(i))).ge.t) p1=i
   2 continue
      if (pl.ne.0) go to 25
c no packets discarded.
      if (pl.eq.0) go to 30
c packet discarded and stack count adjusted.
c check individual packet loss rate
  25 rf=f
      rp1=s(p1)
      do 1000 i=1.f
      ri=i
      z=(rpl-ri)/rf
      ix=z
      y=ix
      if (z.eq.y) nd1(i)=nd1(i)+1
 1000 continue
      if (pl.eq.nst) go to 26
      if (pl.ne.nst) go to 27
  26 nst=nst-1
      nd=nd+1
      write(*,*)'nd=',nd,'ct=',ct,'s(i)=',s(i)
      go to 20
  27 p2=p1+1
      do 3 i=p2, nst
      s(i-1)=s(i)
      r(i-1)=r(i)
   3 continue
      nst=nst-1
      write(*,*)'nd=',nd,'ct=',ct,'s(i)=',s(i)
      qo to 20
```

c determine length of step forward.

```
30 nt=0
      if (nst.eq.0) go to 15
      p3=0
      do 4 i=1, nst
      if (r(i).eq.0) nt=nt+1
      if (r(i).eq.0) p3=i
   4 continue
      if (nt.eq.0) go to 35
      if (nt.eq.1) go to 37
      if (nt.gt.1) go to 50
c no packets in tx cell, adjust stack, increase ct
c and check for new arrivals.
  35 ct=ct+1
      do 5 i=1, nst
      r(i)=r(i)-1
   5 continue
      go to 10
  37 ns=ns+1
      if (p3.eq.nst) go to 39
      if (p3.ne.nst) go to 38
  38
      p2=p3+1
      do 6 i=p2, nst
      s(i-1)=s(i)
      r(i-1)=r(i)
     continue
   6
C
  39
     nst=nst-1
      if (nst.eq.0) go to 81
      do 7 i=1, nst
      r(i)=r(i)+m-1
     continue
Ç
  81
      nql=nq+l
      if (nq1.gt.nm) go to 85
      do 8 i=nq1, nm
      if (a(i).ge.(ct+p)) go to 85
      if (a(i).ge.ct.and.a(i).lt.(ct+p)) go to 42
  42 nst=nst+1
      s(nst)=i
c generate a random number between 0 and (m-1) = op
С
      call randi(op)
      r(nst)=op
      ng=ng+1
   8 continue
```

Trictery Depression Learnson metabolica Depression

```
c increase time by packet length.
       ct=ct+p+1
       go to 10
C
  50
      do 9 i=1, nst
       if (r(i).eq.0) go to 53
       if (r(i).ne.0) go to 55
c random number between 1 and n = oj.
  53
       call randj(oj)
       r(i)=r(i)+(m-1)+oj
       go to 9
       r(i)=r(i)+(m-1)+n
       continue
       nq1=nq+1
       if (nq1.gt.nm) go to 75
       do 60 i=nq1, nm
       if (a(i).ge.(ct+b)) go to 75
       if (a(i).ge.ct.and.a(i).lt.(ct+b)) go to 70
С
  70
       nst=nst+1
       s(nst)=i
       nq=nq+1
c random number between 0 and (m-1) = om
       call randi(om)
       r(nst)=om
  60
      continue
c increase time by collision interval.
  75 ct=ct+b+1
       go to 10
       plr=(real(nd)/real(nm))*100.
       write (*,*) '# voice ckts =',f
write (*,*)'p='.p.'t='.t
                  *)'p=',p,'t=',t
       write (*,*)'p=',p, t-,t
write (*,*)'nm=',nm,'m=',m,'n=',n
write (*,*)'ns=',ns,'nd=',nd,'ct=',ct
write (*,*)'packet loss rate=',plr,'%'
       write(1,*)'# voice ckts =',f
write(1,*)'p=',p,'t=',t
write(1,*)'nm=',nm,'m=',m,'n=',n
       write(1,*)'ns=',ns,'nd=',nd,'ct=',ct
       write(1,*)'packet loss rate =',plr,'%'
       write(*,*) (nd1(i), i=1,f)
```

AND LEAST TOURS OF THE STATE OF

```
write(1,*) (nd1(i), i=1,f)
      stop
      end
c subroutine to generate uniformly distributed random numbers
c between 0 and m-1.
      subroutine randi(x)
      integer lo, hi, l, c, m, seed, x
      real randu
      10=0
      hi=0
      1=29
      c = 217
      m = 1024
      data seed /433/
      seed=mod(seed*l+c,m)
      randu=real(seed)/m
      x=int(randu*(max(lo,hi)-min(lo,hi)+1))
c subroutine to generate uniformly distributed random numbers
c between 1 and n.
      subroutine randj(x)
      integer lo, hi, l, c, m, seed, x
      real randu
      10=1
      hi=4
      1=29
      c = 217
      m = 1024
      data seed /341/
      seed=mod(seed*l+c,m)
      randu=real(seed)/m
      x=(int(randu*(max(lo,hi)-min(lo,hi)+1))+1)
c subroutine to generate packets, uniformly distributed over 0 to
c T.
      subroutine randa(x)
      integer lo, hi, l, c, m, seed, x
      real randu
      10=0
      hi=449
      1=29
      c = 217
      m = 1024
      data seed /9873/
      seed=mod(seed*l+c,m)
      randu=real(seed)/m
      x=int(randu*(max(lo,hi)-min(lo,hi)+1))
      end
```

**ᡱᡚᠻᢒᡶᡚᡶᡚᡌ᠘ᡚᡳᡚᡳᡚᡳᡚᠺᡚᡚᢗᡮᡚᢗᡮ᠒ᡶᡚᡶ᠘ᡶᢗ**ᡚᡳᠿᡳᢓᡙᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚᡚ᠘

- [1] Musser, Jeffrey M.; Liu, Then Tang; Li, Liang; and Boggs, George J. "A Local Area Network as a Telephone Local Subscriber Loop." IEEE Journal on Selected Areas in Communications SAC-1, No. 6 (December 1983): 1046-
- Metcalfe, R.M., and Boggs, D.R. "Ethernet: Distributed Packet Switching for Local Computer Networks." Commun. Ass. Comput. Mach. 19, No. 7 (1976): 395-403.
- [3] Liu, T.T; Li, L.; and Franta, W.R. "A Decentralized Conflict-Free Protocol, GBRAM for Large Scale Local Networks." In Proc. Comput. Network. Symp. (December
- [4] Merakos, L. "Stack Algorithm for Local Area Networks Using Carrier Sense Multiple Access Channels." Technical Report, University of Connecticut, Storrs, CT, 1983.
- REFERENCES

  [1] Musser, Jeffrey M.; Liu, Then Tang; Li, Liang; and George J. "A Local Area Network as a Telephy Subscriber Loop." IEEE Journal on Selected Jommunications SAC-1, No. 6 (December 1983): 1053.

  [2] Metcalfe, R.M., and Boggs, D.R. "Ethernet: Distracket Switching for Local Computer Networks Ass. Comput. Mach. 19, No. 7 (1976): 395-40.

  [3] Liu, T.T.; Li, L.; and Franta, W.R. "A Decentrality Conflict-Free Protocol, GBRAM for Large Scale Networks," In Proc. Comput. Network, Symp. 1981): 39-54.

  [4] Merakos, L. "Stack Algorithm for Local Area Networks, The Proc. Comput. Network, Symp. 1981): 39-54.

  [5] Georgiopoulos, M.; Merakos, L.; and Papantoni-Kaz. "High Performance Asynchronous Limited Sensi Algorithms for CSMA and CSMA/CD Channels." Area and Multiple Access Networks, pp. 185-2 by R.L. Pickholtz. New York: Computer Scie 1986.

  [6] Tsybakov, B.S., and Vvedenskaya, N.D. "Stack Alg. Random Multiple Access." Problemy Peredachi Informatisi 1s, No. 3 (Juliy/September 1980):

  [7] Brady, P.T. "A Technique for Investigating On-Of of Speech." Bell Sys. Tech. Journal 44 (Jami-1-22.

  [8] Brady, P.T. "A Statistical Analysis of On-Off Pasixteen Conversations." Bell Sys. Tech. Journal (January 1968): 73-91.

  [9] Schwartz, M. Telecommunication Networks. New York Addison Wesley, 1987. Georgiopoulos, M.; Merakos, L.; and Papantoni-Kazakos, P. "High Performance Asynchronous Limited Sensing Algorithms for CSMA and CSMA/CD Channels." In Local Area and Multiple Access Networks, pp. 185-215. Edited by R.L. Pickholtz. New York: Computer Science Press,
  - "Stack Algorithm for Informatsii 15, No. 3 (July/September 1980): 80-94.
  - Brady, P.T. "A Technique for Investigating On-Off Patterns of Speech." Bell Sys. Tech. Journal 44 (January 1965):
  - Brady, P.T. "A Statistical Analysis of On-Off Patterns in Sixteen Conversations." Bell Sys. Tech. Journal 47
  - Schwartz, M. Telecommunication Networks. New York:

# -ILMED 8